

1695

OFFICE OF THE
MUNICIPAL COMMITTEE
JHANG
Telephone & Fax No 047-
9200347
Email:mcjhang347@gmail.com

To

M/S Shad Construction Company
Street No. 2/A Haideria road, Gulgasht Colony Multan

(Award Letter)

No 415/Moi dated 17/7/2023

Subject: **PROVIDING & LAYING OF TUFF PAVER IN STREET OF MC JHANG**

This is with reference to your Financial Bid submitted on 23.05.2023 for execution of "Providing & Laying of Tuff paver in Street of MC Jhang after completing the process of bidding. The rate of your bid for the scheme cited as subject has been approved by the competent authority with the completion period of (17.01.2024) starting from the date of issuance of this letter as per approved items rate of Financial bid.

Your Firms M/S Shad Construction Company Street No. 2/A Haideria road, Gulgasht Colony Multan has been declared as "**Successful Bidder**" for "Providing & Laying of Tuff paver in Street of MC Jhang" is being technically responsive and lowest evaluation bidders.

Municipal Committee Jhang hereby accepts the bid of your Firm as per recommended by Jers Consultancy Pvt Ltd Lahore.

| Sr. # | Description | Unit | Qty | Unit Rate (Rs.) | Amount (Rs.) |
|-------|---|---------|---------|-----------------|--------------|
| 1 | Scarifying old road surface including removal of debris within 1 chain (30 m). | 100 Sft | 3203.97 | 438.00 | 1,403,339 |
| 2 | Earthwork excavation in open cutting upto 5'-0" (1.5 m) depth for storm water channels, drains, sullage drains in open areas, roads, streets, lanes, including under pinning of walls and shoring to protect existing works, shuttering and timbering the trenches, dressed to designed level and dimensions, trimming, removal of surface water from trenches, back filling and surplus excavated material disposed of and dressed within 50 ft. (15 m) lead:- | | | | |
| | i) ordinary | 1000Cft | 51.82 | 9,260.00 | 479,853 |
| 3 | Compaction of earthwork with power road roller, including ploughing, mixing, moistening earth to optimum moisture content in layers, etc. complete. i) 95% to 100% maximum modified AASHO dry density. | 1000Cft | 60.18 | 1,418.00 | 85,335 |

B

| | | | | | |
|----|---|--------|-----------|-----------|------------|
| 4 | Providing and laying sub-base course of stone product of approved quality and grade including, placing, mixing, spreading and compaction of sub base material to required depth, camber and grade to achieve 98% maximum dry density determined according to AASHTO T-180 method-D, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment) | 100Cft | 276.34 | 15,170.00 | 4,192,078 |
| 5 | Providing and laying road edging of 3" (75 mm) wide and 9" (225 mm) deep brick on end, complete in all respects. | Prft | 8750.00 | 50.00 | 437,500 |
| 6 | Providing and laying base course of crushed stone (Water Bound Macadam) of approved quality and grade including, placing, mixing, spreading and compaction of base course material to required depth, camber and grade to achieve 100% maximum modified AASHTO dry density, including carriage of all material to site of work complete in all respect as per specifications and as directed by the engineer incharge. (Crushed stone aggregate from Sargodha quarry to site, actual compacted depth shall be considered for payment) | 100Cft | 1,341.20 | 19,977.00 | 26,793,152 |
| 7 | Providing and laying Tuff pavers, having 7000 PSI, crushing strength of approved manufacturer, over 2" to 3" sand cushion i/c grouting with sand in joints i/c finishing to require slope. complete in all respect. (50% Grey / 50% Coloured) | | | | |
| | c) 80-mm thick | Sft | 430272.80 | 201.85 | 86,850,565 |
| 8 | c) Dismantling cement concrete 1:2:4 plain. | 100Cft | 41.23 | 11,464.00 | 370,860 |
| 9 | Dismantling brick or flaged flooring wihtout concrete | 100Sft | 129.17 | 885.00 | 21,107 |
| 10 | Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate): | | | | |
| | (f) Ratio 1: 2: 4 | 100Cft | 74.68 | 36,400.00 | 2,718,352 |
| 11 | Pacca brick work other than building upto 10ft. (3 m) Cement, sand mortar:- Ratio 1:3 | 100Cft | 57.10 | 31,458.00 | 5,998,411 |
| i | Pacca brick work other than building upto 10ft. (3 m) Cement, sand mortar:- Ratio 1:3 | 100Cft | 64.26 | 31458.00 | 20,21,491 |

Di

1899

| | | | | | |
|----|--|--------|----------|-----------|-----------|
| ii | Pacca brick work other than building upto 10ft. (3 m) Cement, sand mortar:- Ratio 1:3 | 100Cft | 69.23 | 32708.00 | 22,64,375 |
| 12 | Extra for pacca brick work in steining of wells or any other circular masonry. | 100Cft | 9.97 | 2,708.00 | 26,999 |
| 14 | Cement plaster 1:3 upto 20' (6.00 m) height:- | | | | |
| | b) ½" (13 mm) thick | 100Sft | 266.90 | 3,420.00 | 912,798 |
| 15 | Constructing standard gully grating chamber, 3'x2½' (900x750 mm), with chinaware trap as per PHED Drawing STD/PD No. 3 of 1977, complete in all respects. | Each | 65.00 | 16,025.00 | 1,041,625 |
| 16 | Supplying and filling sand under floor or plugging in wells. | 100Cft | 24.38 | 2,803.00 | 68,337 |
| 17 | Providing, fixing, testing and commissioning of µ-PVC (Unplasticized polyvinyl Chloride) Nikasi /waste pipe make of dadex / Popular / Beta/ BBJ plain / socket ended conforming to code EN-1401 of specified SDR (Standard Dimension Ratio) including the cost of specials and Solvents complete in all respect as approved and directed by the Engineer Incharge. | | | | |
| | (vii) 8"(200 mm) | Rft | 725.00 | 427.00 | 309,575 |
| 18 | Carriage of 100 Cft. (2.83 cu.m) of all materials like stone aggregate, spawl, kankar lime (unslaked), surkhi, etc. or 150 Cft. (4.25 cu.m) of timber, by truck or by any other means owned by the contractor. (crushed stone aggregate and bajri used in concrete items) (Lead 105 Km) | Cft | 6,571.84 | 70.00 | 460,029 |
| 19 | Providing and fixing RPC Manhole Cover Manufactured with 100% Reinforced Plastic Composite Material, 650 mm dia with clear opening size 600 mm (24" dia) and RPC manhole frame having dia meter 790 mm (Complete) (Certified under ISO 9001-2015) | Each | 185.00 | 11,471.00 | 2,122,135 |
| 20 | Old/existing Manhole cover and Frame complete set shift to MC store. | Set | 185.00 | 470.00 | 86,950 |
| 21 | Providing, fabrication and fixing pole mounted Direction Board/ road delineator of any shape and size, with specified Sheet and thickness, supported with G.I Channel, (excluding the cost of vertical post and painting) etc complete in all respect. | Sft | 12.00 | 937.00 | 11,244 |

A

179

| | | | | | |
|---|--|--------|--------|-----------|---------|
| 22 | Providing, fabrication and fixing Vertical Post comprising of medium quality G.I Pipe of specified diameter, including the cost of clamping arrangements, top cover, hold fasts embedded in PCC 1:2:4 etc, complete in all respect | Rft | 22.00 | 1445.00 | 31,790 |
| 23 | Lettering and printing of signage /direction boards/ road delineators of any colour by machine i/c cost of Digital Lettering, Lamination & pasting etc complete in all respect. | Sft | 12.00 | 1130.00 | 13,560 |
| 24 | Providing and fixing precast Edge Kerb Stone (4" to 6" thick), of 3500 PSI Compressive Strength, embedded in PCC 1:2:4 over lean concrete 1:4:8 etc. complete in all respect. | Rft | 450.00 | 503.00 | 226,350 |
| 25 | Deduction of used bricks from original quantity | 100Cft | 65.38 | 5640.00 | 368,743 |
| ENVIRONMENTAL MITIGATION & MANAGEMENT COST | | | | | |
| 1 | Face Masks (3 PLY) - box | Nos | 25.00 | 300.00 | 7,500 |
| 2 | Safety Hard Helmets | Nos | 10.00 | 3000.00 | 30,000 |
| 3 | Safety Shoes | Nos | 10.00 | 3000.00 | 30,000 |
| 4 | Hand Glovessc | Nos | 10.00 | 1000.00 | 10,000 |
| 5 | Ear Plugs | Nos | 10.00 | 500.00 | 5,000 |
| 6 | Reflective Safety Vest | Nos | 10.00 | 1000.00 | 10,000 |
| 7 | Safety Goggles | Nos | 10.00 | 500.00 | 5,000 |
| B-Community Health and Safety | | | | | |
| 1 | First Aid Box Co+B58:F67mplete | Nos | 1.00 | 10000.00 | 10,000 |
| 2 | Safety Signs | Nos | 3.00 | 10000.00 | 30,000 |
| 3 | Safety Cones | Nos | 20.00 | 1000.00 | 20,000 |
| 4 | Safety Tapes | Nos | 50.00 | 1500.00 | 75,000 |
| 5 | Portable Delineator with chain | Nos | 3.00 | 2200.00 | 6,600 |
| 6 | Emergency Portable Lights | Nos | 3.00 | 3000.00 | 9,000 |
| 7 | Solid Waste Collection Drums with Cover | Nos | 3.00 | 12000.00 | 36,000 |
| 8 | Fire Fighting Equipment Purchase and refilling | Nos | 1.00 | 10000.00 | 10,000 |
| 9 | BCC Campaign and waste collection system | Nos | | 100000.00 | 100,000 |
| 10 | Water Sprinkling | Nos | | 100000.00 | 100,000 |

1. The total bid price (herein after referred to as "Total Contract price" shall be governed for the completion of the entire work related to the project, as per terms and conditions set forth in the bidding documents, BOQ, Specifications, Drawings, addendums and the contract of the subject project.
2. The work shall be carried out by you strictly in accordance with the Scope of work as well as other terms and conditions as given in the bidding documents.
3. The Contract Agreement will be executed on Rs. 10000/- (Rupees Ten Thousand) stamp paper as per specimen provided in bidding documents.

Dr

17/07/23

4. If the foregoing is acceptable to you, please sign and return the duplicate copy of this Letter of Award in token of your acceptance and depute your authorized representative to execute a formal contract agreement with Municipal Committee Jhang at the earliest please.
5. Joint venture agreement on legal paper & Power of Attorney in case must be provided before work order. It must be clearly mentioned on the legal paper which will be the payment account either joint venture account or individual bank account.


CHIEF OFFICER
MUNICIPAL COMMITTEE
JHANG


CC:

1. The Administration, MC Jhang
2. The Municipal Officer (I&S), MC Jhang



On Behalf of
M/S Shad Construction Company
Street No. 2/A Haideria road, Gulgasht
Colony Multan

Received, Agreed & Accepted
Name: M/s Shad Const. Co
Signature: 
Stamped _____
Dated: 18-07-2023
M/s Shad Construction Co
MULTAN